

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21049-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 2-25S-5E  
3215 feet from S Section Line, 4040 feet from E Section Line  
Lease Name: STONE Well #: 24  
County: BUTLER Total Vertical Depth: 2536 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2490		
SURF	8.625	205		150 SX
PROD	5.5	2536	292	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2011 8:00 AM  
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.  
Proposal Rcvd. from: ROB WILLIAMS Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/23/2011 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @2360'. DUMP BAILED 2 SXS CEMENT ON TOP OF CIBP. SDON. 9-23-2011, COMPLETED CELLER WORK, RIH ON WIRELINE, CUT CASING @ 292', LAYED DOWN 7 JTS 5-1/2" CASING (292'). RIH W/TBG @ 260', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 103 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 PM, 9-23-2011. CONSOLIDTED CEMENT TICKET #31745.

Perfs:

Top	Bot	Thru	Comments
2500	2502	CSG	
2412	2416	CSG	

Remarks:  
Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

10/10/11  
RECEIVED  
OCT 05 2011  
KCC WICHITA