

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20703-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 24-21S-2W
1855 feet from S Section Line, 3383 feet from E Section Line
Lease Name: HUXMAN-KREHBIEL Well #: 2
County: MCPHERSON Total Vertical Depth: 3395 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	125		100 SX
PROD	4.5	3379	1512	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2011 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRAVIS HAMM Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/23/2011 1:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

9/20/11 KELSO'S DROPPED SAND. 9/21/11 KELSO'S TAGGED SAND @ 3325' AND CAPPED W/4 SX. THEY PULLED STRETCH IN CASING AND RIPPED IT @ 1512'. THEY PULLED UP TO 400'. COPELAND TIED ON AND SPOTTED 150 SX COMMON W/3% CC AND 2 BAGS HULLS. 9/23/11 COPELAND OUT AND RAN POLY PIPE DOWN THE HOLE TAGGING CEMENT @ 90'. CIRCULATED THE HOLE FULL WITH 35 SX 60/40 POS 4% GEL. TK #37269. 9/24/11 I CHECKED TOP PLUG DOWN 4'. OPERATOR WILL TOP OFF WHEN DRESSING UP LOCATION.

Perfs:


Top	Bot	Thru	Comments
3378	3390	OH	

Remarks: DENIED TA DUE TO HIGH FLUID LEVEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT 05 2011

10/10/11

KCC WICHITA