

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20105-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 24-21S-2W  
350 feet from S Section Line, 3670 feet from E Section Line  
Lease Name: HUXMAN-KREHBIEL OWWO Well #: 4  
County: MCPHERSON Total Vertical Depth: 3445 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	266		250 sx
PROD	4.5	3429	288	135 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2011 1:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2011 4:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

9/26/2011 KELSO'S DROPPED SAND. 9/27/11 KELSO'S TAGGED SAND @ 3300' AND CAPPED W/4 SX. THEY PULLED STRETCH IN CASING AND IT PARTED @ 288'. THEY PULLED THE 4.5" AND LAID IT OUT. THEY ARE RUNNING BACK IN WITH 2" TUBING TO 400', AND THEN COPELAND WILL PERF CASING @ 400' AND SPOT A 35 SX HOT PLUG. KELSO'S CAN NOT GET BACK INSIDE CASING. THEY CAN GET DOWN TO 375' ON THE BACKSIDE OF 4.5". COPELAND SPOTTED A 50 SX COMMON W/3% CC. KELSO'S PULLED TUBING OUT AND WE WAITED A LITTLE OVER AN HOUR. KELSO'S RAN TUBING BACK DOWN AND TAGGED CEMENT @ 320'. THEY PULLED BACK UP TO 285'. COPELAND TIED BACK ON AND CIRCULATED CEMENT TO SURFACE W/ 170 SX 60/40 POS 4% GEL. TK #37272. 9/28/11 I CHECKED TOP PLUG AND FOUND IT @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
3374	3378	CSG	Hunton

Remarks: APPROVED TA ON 5/2011

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

RECEIVED Form CP-2/3  
OCT 05 2011 10/10/11

KCC WICHITA

sk