

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40178-00-00
Spot: SESWNESW Sec/Twnshp/Rge: 19-26S-5E
1599 feet from S Section Line, 3576 feet from E Section Line
Lease Name: HOUSTON Well #: 18
County: BUTLER Total Vertical Depth: 2466 feet

Operator License No.: 34426
Op Name: AJ'S SERVICES, A GENERAL PARTNER
Address: 924 N. TOPEKA ST. PO BOX 1118
ELDORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		75 SX
PROD	5.5	2466		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2011 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: JOHN BRICKLEY Company: AJ'S SERVICE Phone: (316) 322-7478

Proposed Plugging Method: AS PER KCC RULES & REGS, 6 SXS CEMENT ON BOTTOM W/DUMP BAILOR, PULL TOP 300' CASING, RUN 2" TBG TO ROCK BRIDGE @ 250', PUMP CEMENT TO SURFACE

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 09/26/2011 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/WORKSTRING CIRCULATING HOLE CLEAN @ 2292', CIRCULATING SCALE & MUD BACK TO SURFACE. W/WORKSTRING @2290', CONSOLIDATED WELL SERVICES MIXED & PUMPED 40 SXS 60/40 POZMIX 2% GEL, 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2064'. SDON. 9-26-2011, PERFORATED SQUEEZE HOLES @ 250'-251', RIH W/TBG @ 250', CONSOLIDATED MIXED & PUMPED 275 SXS 60/40 POZMIX 4% GEL 1% CC TO CELLER. PLUG DOWN 3:30 PM 9-26-2011. CONSOLIDATED SERVICES CEMENT TICKET #31722, 9-27-2011, TOPPED WELL BACK TO SURFACE DRY DUMPED W/27 SXS POZMIX 4% GEL, P&A COMPLETE.

Remarks: PLUG DUE TO COMPLIANCE / 10 YR TA RULE

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
Form CP-2/3
OCT 05 2011 10/10/11

KCC WICHITA