

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-21039-00-00  
Spot: SWNWSESW Sec/Twnshp/Rge: 29-11S-34W  
825 feet from S Section Line, 1343 feet from W Section Line  
Lease Name: PETERSON Well #: 1-29  
County: LOGAN Total Vertical Depth: 4902 feet

Operator License No.: 34601  
Op Name: WOLD OIL PROPERTIES, INC.  
Address: 130 W. 2ND ST., STE 200  
CASPER, WY 82601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 222        |             |          |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2011 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE  
Date/Time Plugging Completed: 10/02/2011 7:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 2666' w/25 sxs.  
2nd. Plug at 1600' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

10/10/11

OCT 03 2011

RECEIVED  
OCT 07 2011  
KCC WICHITA