

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26154-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 6-15S-18W
1507 feet from S Section Line, 2307 feet from E Section Line
Lease Name: WALT DECHANT Well #: 2
County: ELLIS Total Vertical Depth: 3671 feet

Operator License No.: 33457
Op Name: DECHANT, WALTER DBA DECHANT OI
Address: 503 W 30TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	916	0	375 SX
PROD	5.5	3670	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2011 9:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: DECHANT OIL COMPANY Phone: (785) 625-5281

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2011 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log-Tech set a CIBP over LKC perfs at 3234'.
Log-Tech shot off casing at 1570'.
Quality rigged to casing and pumped 125 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled casing to 1213'. Quality rigged to casing and pumped 50 sxs cement with 100# hulls mixed in.
Pulled casing to 568'. Quality rigged to casing and pumped 75 sxs cement with 100# hulls mixed in.
Pulled casing to 164'. Quality rigged to casing and pumped 45 sxs cement to circulate cement to surface.
Pulled casing. 8 5/8" casing standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3292	3605		LKC / ARBUCKLE


RECEIVED
OCT 07 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5178.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

10/10/11

OCT 03 2011