

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23983-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 29-9S-20W  
2200 feet from N Section Line, 2050 feet from W Section Line  
Lease Name: GRAHAM A Well #: 3  
County: ROOKS Total Vertical Depth: 3950 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2011 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: JAY Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 09/30/2011 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3862' w/25 sxs.  
2nd. Plug at 1805' w/25 sxs.  
3rd. Plug at 1075' w/100 sxs.  
4th. Plug at 310' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

RECEIVED  
OCT 07 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

CM

Form CP-2/3

10/10/11

OCT 03 2011