

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20514-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 5-25S-17W
4296 feet from S Section Line, 2275 feet from E Section Line
Lease Name: MUNDHENKE Well #: 1-5
County: EDWARDS Total Vertical Depth: 4600 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4000 | | WITH 2 SX CMT |
| SURF | 8.625 | 600 | | WITH 325 SX CMT |
| PROD | 4.5 | 4600 | 0 | WITH 200 SX CMT |
| RBP | | 4170 | | |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/26/2011 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4000' WITH 2 SX CMT ON TOP. PERFORATE 5 1/2" AT 1100'. RUN TBG TO 1100'. PUMP CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2011 1:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4000' & PLACED 2 SX CMT ON TOP WITH DUMP BAILER. PERFORATE 5 1/2" @ 1100'. RAN TBG TO 1099'. PUMPED 380 SX CMT CIRCULATING TO SURFACE UP THE 4 1/2" & THE 8 5/8" X 4 1/2" ANNULUS. PULLED TBG OUT OF HOLE & TOPPED IT OFF WITH 15 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4083 | 4085 | | |

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
SEP 29 2011
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

Form CP-2/3

10/12/11