

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20404-00-00  
Spot: SENE Sec/Twnshp/Rge: 26-2S-19W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HANKE Well #: 1-26  
County: PHILLIPS Total Vertical Depth: 3427 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	301	0	185 SX
PROD	4.5	3529	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2011 10:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: BEREXCO, LLC Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Perforated at 350' - 950' - 1750'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2011 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3380' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 2211' - pumped 130 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 400# immediately.

Perfs:

Top	Bot	Thru	Comments
3432	3434		
3388	3390		
3370	3372		
3364	3365		
3315	3317		
3272	3274		
3268	3270		
3234	3434		
3153	3155		
3118	3121		
2511	2546		
1964	2034		

RECEIVED  
OCT 11 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38306.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

10/12/11

OCT 06 2011