

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03049-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 24-9S-19W
1980 feet from S Section Line, 4950 feet from E Section Line
Lease Name: JELINEK Well #: 4
County: ROOKS Total Vertical Depth: 3580 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	274	0	125 sxs
PROD	5.5	3574	0	100 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2011 11:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.
Arbuckle 3574'. Casing leaks.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2011 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline perfed at 925' - 1590'. Holes in the casing at 2000'.
Bowman Oil RIH with tubing to 3500'.
Allied rigged to tubing and pumped 9 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.
Pulled tubing to 2170'. Allied rigged to tubing and pumped 130 sxs cement with 350# hulls mixed in.
Pulled tubing to 1085'. Allied rigged to tubing and pumped 50 sxs to circulate cement to surface.
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Rigged to 8 5/8" casing - pumped 35 sxs cement.
Max. P.S.I. 150#. S.I.P. 50#.

Perfs:


RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37286.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

10/2/11

OCT 06 2011