

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23498-00-00
Spot: NWSWNSW Sec/Twnshp/Rge: 34-10S-20W
1800 feet from S Section Line, 1450 feet from W Section Line
Lease Name: VEATCH Well #: 1
County: ROOKS Total Vertical Depth: 3730 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260	0	200 SX COMMON CMT
T1	2.875	3630		
PC		1617		180 SX CMT
PROD	5.5	3730	0	150 SX ASC CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2011 4:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DONALD BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel. CIBP at 3650'. PC at 1617' w/180 sxs cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2011 7:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing - pumped 75 sxs cement with 300# hulls mixed in - followed with 12 sxs gel - followed with 150 sxs 60/40 pozmix with 200# hulls mixed in.
Max. P.S.I. 800#. S.I.P. 600#.
Rigged to 8 5/8" casing and pumped 15 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3708	3730		
3604	3608		
3510	3514		
3420	3425		


RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37287.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

10/12/11

OCT 06 2011