

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20540-00-00  
Spot: NWSE Sec/Twnshp/Rge: 10-34S-34W  
1934 feet from S Section Line, 1973 feet from E Section Line  
Lease Name: MCGILL A Well #: 1  
County: SEWARD Total Vertical Depth: 6530 feet

Operator License No.: 34408  
Op Name: CISCO OPERATING LLC  
Address: 6900 N. DALLAS PKWY, STE 740  
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6042		WITH 2 SX CMT
CIBP		6080		
CIBP		6400		
SURF	8.625	1668		WITH 800 SX CMT
PROD	4.5	6528	2804	WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2011 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: SAUL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 6042' w/ 2 sks cement . Load hole w/ mud . Cut & pull +/- 2500' - 4 1/2" casing . Run tbg @ 1700' & spot 80 sks cement . Pull up to 650' & spot 60 sks cement . Top out 64' - 4' w/ 20 sks cement.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/07/2011 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 6042' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 80 SX CMT. 2ND PLUG AT 650' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6404	6412		CHESTER
6370	6396		CHESTER
6110	6116		CHESTER
6092	6100		CHESTER
6044	6050		

RECEIVED  
OCT 11 2011  
KCC WICHITA


Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
SEP 30 2011  
KCC DODGE CITY

Signed



(TECHNICIAN)

Form CP 2/3

10/12/11