

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20716-00-01
Spot: W2E2NWNE Sec/Twnshp/Rge: 32-4S-36W
660 feet from N Section Line, 1960 feet from E Section Line
Lease Name: WISMAN MANETT Well #: 1-32
County: RAWLINS Total Vertical Depth: 4810 feet

Operator License No.: 8628
Op Name: CREDO PETROLEUM CORPORATION
Address: 1801 BROADWAY # 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	352	0	w/unknown sxs cmt
PROD	5.5	4779	0	w/unknown sxs cmt

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/04/2011 8:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: JACK RENFRO Company: CREDO PETROLEUM CORPORATI Phone: (303) 297-2200

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through tubing and casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2011 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

10-04-2011 - 8 5/8" surface casing set at 352' w/unknown sxs cement.
Well formerly known as Manett Wisman #32-1 - plugged as D&A on June 4, 1988.
Re-entered and washed down to 4910'.
5 1/2" production casing set at 4903' with 50 sxs scavenger cement and 150 sxs ASC.
DV tool cemented with 60 sxs cement.
Well determined to be non-commercial.
Ran tubing to 4100' - pumped 50 sxs cement mixed with 100# hulls.
Pulled tubing to 3160' - pumped 40 sxs cement mixed with 50# hulls.
Pulled tubing OOH. Cut 5 1/2" production casing at 2450'.
Could not pull 5 1/2" casing.
Perforated 5 1/2" casing at 2415' with 6 shots.
Connected to 5 1/2" - loaded casing with water and pressured to 800#.
Could not pumped into perforations.
Cut casing at 1986' - casing free.
Pulled one joint. Shut down at 5:30 P.M.
10-05-2011 - Pumped 75 sxs cement with 150# hulls at 1946'.
Pulled casing to 400' - pumped 75 sxs cement mixed with 150# hulls.
Pumped 20 sxs cement from 40'.
Cement to surface.

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: S.O.S. CEMENT SERVICES-TICKET #535.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

10/12/11

OCT 05 2011