

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21277-00-00
Spot: NWSE Sec/Twnshp/Rge: 2-24S-17W
2022 feet from S Section Line, 1945 feet from E Section Line
Lease Name: MEALS Well #: 3-2
County: EDWARDS Total Vertical Depth: 4445 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4384		
SURF	8.625	310		WITH 225 SX CMT
PROD	4.5	4442	1980	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2011 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4220' & 4 SX CMT ON TOP OF SAND. 1ST PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 340' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2011 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4200' & 4 SX CMT ON TOP OF SAND WITH A DUMP BAILER. 1ST PLUG AT 1085' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 372' WITH 50 SX CMT. 4TH PLUG AT 62' WITH 30 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:

Top	Bot	Thru	Comments
4277	4324		Mississippian

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 29 2011
KCC DODGE CITY

Form CP-23
10/12/11