

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20924-00-00
Spot: SENE Sec/Twnshp/Rge: 5-20S-16W
3035 feet from S Section Line, 524 feet from E Section Line
Lease Name: NELSON Well #: 1-B
County: PAWNEE Total Vertical Depth: 3900 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	830		WITH 225 SX CMT
PROD	4.5	3900	1512	WITH 175 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/21/2011 10:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3710' WITH 4 SX CMT. 1ST PLUG AT 1110' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 860' WITH 50 SX CMT. 3RD PLUG AT 420' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN
Date/Time Plugging Completed: 09/21/2011 4:15 PM

WitnessType: COMPLETE (100%)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 3682' WITH 4 SX CMT. 1ST PLUG AT 1102' WITH 11 SX GEL & 50 SX CMT. 2ND PLUG AT 860' WITH 50 SX CMT. 3RD PLUG AT 420' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3807	3810		
3759	3763		
0			

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

SEP 30 2011

KCC DODGE CITY

Form CP-207
10/12/11