

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 3956  
Name: Brungardt Oil & Leasing, Inc.  
Address 1: PO Box 871  
Address 2: \_\_\_\_\_  
City: Russell State: KS Zip: 67665 + \_\_\_\_\_  
Contact Person: Gary Brungardt  
Phone: (785) 483-4975  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 141-20,430-00-00  
Spot Description: SW-SE-NE-NE  
\_\_\_\_\_  
\_\_\_\_\_  
Sec. 23 Twp. 10 S. R. 15  East  West  
1,275 Feet from  North /  South Line of Section  
515 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Osborne  
Lease Name: Ruggels "A" Well #: 1  
Date Well Completed: 8-31-11  
The plugging proposal was approved on: 8-31-11 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 9-1-2011  
Plugging Completed: 9-1-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	217'	Cmtd. w/150 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 3,589', pump 25 sax cement thru drill pipe; run drill pipe to 1,100', pump 25 sax cement thru drill pipe; run drill pipe to 650', pump 100 sax cement thru drill pipe; run drill pipe to 275', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Plugging Contractor License #: 5184 Name: Shields Drilling Co.  
Address 1: PO Box 709 Address 2: \_\_\_\_\_  
City: Russell State: KS Zip: 67665  
Phone: (785) 483-3141  
Name of Party Responsible for Plugging Fees: Brungardt Oil & Leasing, Inc.  
State of KANSAS County, RUSSELL, ss. \_\_\_\_\_  
Burton Beery Contractor  
(Print Name)  Employee of Operator  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Burton Beery

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 03 2011

KCC WICHITA

AR



# Shields

Russell, Kansas

## WELL LOG

Operator: Brungardt Oil & Leasing, Inc.  
 Well: Ruggels "A" #1  
 Commenced: 8-25-11  
 Completed: 9-01-11  
 Contractor: Shields Drilling Co.

Well Description: 1,275' FNL, 515' FEL  
 NE/4 Sec. 23-10S-15W  
 Osborne Co., KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	217'	Cmtd. w/150' sax

Elevation: 1,894' K.B.

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Sand & shale	750'
Sand	795'
Sand & redbed	1,076'
Anhydrite	1,112'
Redbed & shale	1,580'
Shale	2,430'
Shale & lime	2,900'
Lime	3,609'
Arbuckle	3,700' RTD

RECEIVED  
 OCT 03 2011  
 KCC WICHITA

Notes