

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 14 TWP. 35S RGE. 13 XE/W  
Location as in quarters or footage from lines:

C NW SE NE

ANB KCC

		X	

Lease Owner Danson Oil Corporation

Lease Name Sternberger Well No. 1

Office Address 3033 NW 63rd-Suite 150-E - Oklahoma City, OK 73116

Character of Well (Completed as Oil, Gas or Dry Hole): Oil

Date Well Completed August 19, 1979

Application for plugging filed Sept. 1, 1981

Plugging commenced July 3, 1981

Plugging completed July 4, 1981

Reason for abandonment of well or producing formation

Non-Commercial.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation Miss. Chat Depth to top 4876 bottom 4890 T.D. 4890

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	367'	None
				4 1/2"	4876'	3618'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 296-416 feet to 10-40 feet for each plug set. Spotted 35 sk cement plug on perfs. Top of cement 4577'. Cut 4 1/2" and pulled and recovered 83 jts. (3618.35'). Spotted 60 sk plug 296-416' and 10 sk plug 10-40' Welded on plate to top of 8 5/8" surface pipe 3' below GL.

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 2 1981

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vertical Casing Pullers, Inc. - Box 347 - Pond Creek, OK 73766

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

T. D. Roberson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein-contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. D. Roberson  
3033 NW 63-Suite 150-E, Okla. City, OK  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 19 81

L. L. Underwood  
Notary Public.

My Commission expires: January 7, 1984

