

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31070
Name: Eagle River Energy Corporation
Address 1: 7060 S. Yale, Suite 702
Address 2: _____
City: Tulsa State: OK Zip: 74136
Contact Person: Mark Godsey
Phone: (918) 494-8928
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing-KC Depth to Top: 3322 Bottom: 3450 T.D. 3450
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 147-00926-00-00
Spot Description: _____
NW NW NE Sec. 20 Twp. 1 S. R. 18 East West
330 4950 Feet from North / South Line of Section
230 2310 Feet from East / West Line of Section
EPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Phillips
Lease Name: Hageman A Well #: 2
Date Well Completed: Nov 1957
The plugging proposal was approved on: 07/28/11 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 09/20/11
Plugging Completed: 09/20/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing-KC	oil, water	surface; production	8 5/8"; 5 1/2"	190'; 3448'	None
					RECEIVED
					OCT 11 2011
					KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run in to 2800', spot 50 sx 60/40 4% gel plus 100 sx w/200# c/s hulls. Pull up to 1400' circulate cement to surface w/135 sx w/200# c/s hulls. Lay out tubing. Top off w/25 sx. 8 5/8 backside, mix 50 sx and shut in.

Plugging Contractor License #: 99996 Name: Allied Cementing Co LLC
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: KS Zip: 67665
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Eagle River Energy Corporation
State of Oklahoma County, Tulsa, ss.
Mark P. Godsey, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark P. Godsey

BR



INVOICE

24 S. Lincoln Street
 P.O. Box 31
 Russell, KS 67665-2906
 Voice: (817) 546-7282
 Fax: (817) 246-3361

Invoice Number: 128692
 Invoice Date: Sep 20, 2011
 Page: 1

Bill To:
 Eagle River Energy Corporation
 82A West Hwy 4
 Hoisington, KS 67544

Customer ID	Well Name# or Customer P/O#	Payment Terms	
EaRi	Hageman A #2	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS2-03	Russell	Sep 20, 2011	10/20/11

Quantity	Item	Description	Unit Price	Amount
216.00	MAT	Class A Common	16.25	3,510.00
144.00	MAT	Pozmix	8.50	1,224.00
12.00	MAT	Gel	21.25	255.00
8.00	MAT	Cottonseed Hulls	31.85	254.80
372.00	SER	Handling	2.25	837.00
50.00	SER	Mileage 372 sx @.11 per sk per mi	40.92	2,046.00
1.00	SER	Plug Abandoned Well	1,250.00	1,250.00
100.00	SER	Pump Truck Mileage	7.00	700.00
100.00	SER	Light Vehicle Mileage	4.00	400.00
1.00	CEMENTER	Glenn Ginther		
1.00	OPER ASSIST	Woody O'Neil		
1.00	EQUIP OPER	Ron Bennett		

GREATBEND *[Handwritten Signature]*

LEASE/WELL NO. H. Huffstutter

PROPERTY NO. 100018

LOE 9788

AFE _____

OTHER _____

APPROVAL *[Handwritten Signature]*

RECEIVED
 OCT 11 2011
 KCC WICHITA

Subtotal	10,476.80
COMPANY NO. _____ VENDOR NO. _____	712.42
Total Invoice Amount	11,189.22
Payment/Credit Applied	
TOTAL	11,189.22

ALL PRICES ARE NET, PAYABLE
 30 DAYS FOLLOWING DATE OF
 INVOICE. 1.12% CHARGED
 THEREAFTER. IF ACCOUNT IS
 CURRENT, TAKE DISCOUNT OF
\$ 3039.16
 ONLY IF PAID ON OR BEFORE
Oct 15, 2011

ALLIED CEMENTING CO., LLC. 038287

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell Ks.

DATE <u>9-20-2011</u>	SEC. <u>20</u>	TWP. <u>1</u>	RANGE <u>18</u>	CALLED OUT	ON LOCATION	JOB START <u>2:00 PM</u>	JOB FINISH <u>2:30 PM</u>
LEASE <u>Hageman</u>	WELL # <u>A-2</u>	LOCATION <u>Phillipsburg Ks., 10 N 3 W</u>			COUNTY <u>PHILLIPS</u>	STATE <u>KANSAS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)		4 N 1/2 E 1/4 SW INTO					

CONTRACTOR Bach Well Service

TYPE OF JOB PLUG ABANDONED WELL

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2" DEPTH 2800'

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 1,000 # MINIMUM 500#

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 360 Sx 40 4% GEL

400 # Hulls

EQUIPMENT

PUMP TRUCK CEMENTER Ernie

417 HELPER Woody

BULK TRUCK _____

482 DRIVER Ron

BULK TRUCK _____

_____ DRIVER _____

COMMON	<u>216</u>	@ <u>16.2-</u>	<u>3510.00</u>
POZMIX	<u>144</u>	@ <u>8.50</u>	<u>1224.00</u>
GEL	<u>12</u>	@ <u>21.2-</u>	<u>255.00</u>
CHLORIDE		@	
ASC		@	
	<u>Hulls</u>	@ <u>31.50</u>	<u>254.80</u>
		@	
		@	
		@	
		@	
HANDLING	<u>372</u>	@ <u>2.20</u>	<u>827.00</u>
MILEAGE	<u>111/4 mi</u>	<u>50</u>	<u>2046.00</u>
TOTAL			<u>8126.80</u>

REMARKS:

2" Tubing @ 2800' Spot 50 Sx Next
+100 Sx w/ 200# Hulls. Pulled up to
1400' & Circulated Cement to Surface
w/ 135 Sx Cement & 200# Hulls. Pulled
Tubing & Cap-off w/ 25 Sx Cement
2 5/8 Backside mixed 50 Sx &
Shot in.

THANKS

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>1250.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>100</u>	@ <u>7.00</u>	<u>700.00</u>
MANIFOLD		@	
<u>Cur</u>	<u>100</u>	@ <u>4.00</u>	<u>400.00</u>
		@	

CHARGE TO: George Rice DBA/ Eagle River Energy

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 2350.00

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE _____

SALES TAX (If Any) _____

TOTAL CHARGES 10476.80

DISCOUNT 50/20 IF PAID IN 30 DAYS

RECEIVED
 OCT 11 2011
 KCC WICHITA