

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5259
Name: MAI OIL OPERATIONS, INC
Address 1: 8411 PRESTON RD, STE 800
Address 2: _____
City: DALLAS State: TX Zip: 75225 + 5520
Contact Person: ALLEN BANGERT
Phone: (214) 219-8883
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-163-23981-00-00
Spot Description: _____
SE NE NW SW Sec. 21 Twp. 10 S. R. 20 East West
2,175 Feet from North / South Line of Section
1,200 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: ROOKS
Lease Name: VINZANT Well #: 2
Date Well Completed: 10/05/2011
The plugging proposal was approved on: 10/04/2011 (Date)
by: ED SCHUMACHER (KCC District Agent's Name)
Plugging Commenced: 10/04/2011
Plugging Completed: 10/05/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8 5/8	221	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 230 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal, 1st plug @ 3814' with 25 sacks, 2nd plug @ 1740' with 25 sacks, 3rd plug @ 970' with 100 sacks, 4th plug @ 270' with 40 sacks, 5th plug @ 40 to surface with 10 sacks, 30 sacks for rat hole, by Quality (Ticket #5182), plug was down @ 2:30 pm on 10/5/2011.

RECEIVED
OCT 12 2011

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING
Address 1: 8 NORTH MAIN Address 2: PO BOX 276
City: ELLINWOOD State: KANSAS Zip: 67526 + _____
Phone: (620) 564-3800
Name of Party Responsible for Plugging Fees: MAI OIL OPERATIONS, INC
State of KANSAS County, BARTON, ss.
JILL WAHLMEIER Employee of Operator or Operator on above-described well,
(Print Name)

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

VCC



Southwind Drilling, Inc. Plugging Orders & Reports

Lease: Vinzant #2

Plugging Received from KCC Representative:

Name: ED Schumacher Date: 10-4-11 Time: 3:00 P.M.

1 st plug @ <u>3814</u> feet, <u>25</u> sacks	Stands <u>6 1/2</u>
2 nd plug @ <u>1740</u> feet, <u>25</u> sacks	Stands <u>28</u>
3 rd plug @ <u>970</u> feet, <u>100</u> sacks	Stands <u>15 1/2</u>
4 th plug @ <u>270</u> feet, <u>40</u> sacks	Stands <u>4 1/2</u>
5 th plug @ <u>40</u> feet, <u>10</u> sacks	Stands <u>1</u>

Mousehole: _____ sacks

Rathole: 30 sacks

Total Cement Used: 230 sacks

Type of cement: 60/40 Poz. 4% Gel 1/4" Flo.

Plug Down @ 2:30 P.M. 10-5-11

Call KCC When Completed:

Name: Bruce Basye Date: 10-5-11 Time: 3:30 P.M.

RECEIVED
OCT 12 2011
KCC WICHITA