

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33457
Name: Walter Dechant dba Dechant Oil Company
Address 1: 503 West 30th Street
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Walter Dechant
Phone: (785) 625-5281
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-26,154-00-00
Spot Description: _____
SE SW NW SE Sec. 6 Twp. 15 S. R. 18 East West
1,507 Feet from North / South Line of Section
2,307 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Walt Dechant Well #: 2
Date Well Completed: 10-03-2011
The plugging proposal was approved on: 9-30-2011 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 8:30 AM 10-03-2011
Plugging Completed: 11:30 AM 10-03-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC	salt water	Surface casing	8 5/8"	916'	0
Arbuckle	salt water	Production casing	5 1/2"	3670'	1568'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Arbuckle tested and found noncommercial. CIBP set at 3595'. LKC tested and found noncommercial. CIBP set at 3238'. Pulled stretch in casing and cut off at 1568'. Mixed and pumped 125 sacks of cement with hulls. Pulled casing to 1213' and pumped 50 sacks of cement with hulls. Pulled casing to 568' and pumped 75 sacks of cement. Pulled casing to 164' and circulated cement to surface with 45 sacks. Pulled casing with cement to surface

Plugging Contractor License #: 32128 Name: Western Well Service
Address 1: 1023 Reservation Road Address 2: _____
City: Hays State: Kansas Zip: 67601 + _____
Phone: (785) 625-1118
Name of Party Responsible for Plugging Fees: Walter Dechant
State of Kansas County, Ellis, ss.
Walter Dechant Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Walter Dechant

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 12 2011
10-12-11
KCC WICHITA

[Handwritten mark]