

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 + _____
Contact Person: Dennis Kirmer
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Platts Depth to Top: 2826 Bottom: 2829 T.D. _____
Toronto Depth to Top: 2898 Bottom: 2900 T.D. _____
LKC Depth to Top: 2931 Bottom: 3119 T.D. _____
Arbuckle 3164 3175

API No. 15 - 15.167.30218.00.00
Spot Description: _____
NE NW NW Sec. 31 Twp. 14 S. R. 14 East West
330 Feet from North / South Line of Section
4,290 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Hummel Well #: 4
Date Well Completed: 3-24-66
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 9-16-11
Plugging Completed: 9-16-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Plattsmouth	Oil/Water	Surface	8 5/8	605'	0
Toronto	Oil/Water	Production	5 1/2	3164'	0
L-KC	Oil/Water				
Arbuckle	Oil/Water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2525'. Rig up Allied Cementing. Mix 100 sacks 60/40 poz 4% gel w/100# hulls. Pull tubing to 1400'. Mix 40 sacks cement w/100# hulls. Pull tubing out of hole. Rig up Perf Tech. Shoot 2 holes each @ 780' and 350'. Run tubing to 840' Circulate cement to surface in 5 1/2 and 8 5/8 casing with 135 sacks. Pull tubing out of hole. Top off casing w/15 sacks-hole stayed full. Well Plugged 3:00 P.M. Witnessed by Ray Dinkel-Hays KCC.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Dennis Kirmer Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 13 2011
KCC WICHITA