

**Notice:** Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
March 2009  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

OPERATOR: License #: 6044  
Name: Stelbar Oil Corporation, Inc.  
Address 1: 1625 N. Waterfront Parkway, Suite 200  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + \_\_\_\_\_  
Contact Person: Roscoe Mendenhall  
Phone: ( 316 ) 440-7605  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Viola Depth to Top: 2412' Bottom: 2416' T.D. 2490'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-21049 • 00 • 00  
Spot Description: \_\_\_\_\_  
SE SW NW Sec. 2 Twp. 25 S. R. 5  East  West  
2015 3215 Feet from  North  South Line of Section  
1200 4040 Feet from  East  West Line of Section  
GPS-KCC Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: Stone Well #: 24  
Date Well Completed: 5/78  
The plugging proposal was approved on: September 21, 2011 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Plugging Commenced: September 22, 2011  
Plugging Completed: September 23, 2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Viola	Oil and Saltwater	Surface	8-5/8"	205'	None
		Production	5-1/2"	2536'	300'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2352' and dump two sacks cement on CIBP. Cut 5-1/2" casing at 300' and pull/laydown same. RIH with 2-7/8" tubing to 250'. Circulated 103 sacks cement from 250' to surface. Cement was 60/40 pozmix with 4% gel. POOH with tubing. Cut off 8-5/8" casing 3' below ground and weld on steel plate.

Plugging Contractor License #: 6044 Name: Stelbar Oil Corporation, Inc.  
Address 1: 1625 N. Waterfront Parkway, Suite 200 Address 2: \_\_\_\_\_  
City: Wichita State: Kansas Zip: 67206 + \_\_\_\_\_  
Phone: ( 316 ) 264-8378  
Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.  
State of Kansas County, Sedgwick, ss.  
Roscoe Mendenhall  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


Signature: Roscoe Mendenhall

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

OCT 14 2011

KCC WICHITA



**CONSOLIDATED**  
Oil Well Services, LLC

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 970  
P.O. Box 4346  
Houston, TX 77210-4346

MAIN OFFICE  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 244531

Invoice Date: 09/27/2011 Terms:

Page 1

STELBAR OIL CORP., INC.  
SUITE 200  
1625 N. WATERFRONT PARKWAY  
WICHITA KS 67206-6602  
(316) 264-8378

STONE #24  
31745  
2-25S-5E  
09-23-11  
KS

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	103.00	11.9500	1230.85
1118B	PREMIUM GEL / BENTONITE	400.00	.2000	80.00
Description		Hours	Unit Price	Total
290	P & A OLD WELL	1.00	655.00	655.00
290	EQUIPMENT MILEAGE (ONE WAY)	10.00	4.00	40.00
434	80 BBL VACUUM TRUCK (CEMENT)	2.00	90.00	180.00
442	MIN. BULK DELIVERY	1.00	330.00	330.00

RECEIVED  
OCT 14 2011  
KCC WICHITA

Parts:	1310.85	Freight:	.00	Tax:	85.86	AR	2601.71
Labor:	.00	Misc:	.00	Total:	2601.71		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_

Date \_\_\_\_\_

BARTLESVILLE, OK  
918/338-0808

ELDORADO, KS  
316/322-7022

EUREKA, KS  
620/583-7664

GILLETTE, WY  
307/686-4914

OAKLEY, KS  
785/672-2227

OTTAWA, KS  
785/242-4044

THAYER, KS  
620/839-5269

WORLAND, WY  
307/347-4577



**CONSOLIDATED**  
Oil Well Services, LLC



**ENTERED**

TICKET NUMBER 31745  
LOCATION 180  
FOREMAN LARRY STEAM

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-23-11	7396	Stone #24	2	25 S.	5 EAST	Butler
CUSTOMER STELPAR OIL CORP.			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 1625 N. WATERFRONT PARKWA 200 <sup>suite #</sup>			290	CEVOLD		
CITY Wichita			442	BE R.		
STATE KS			434	TED		
ZIP CODE 67206			539	LARRY		

JOB TYPE Plug B HOLE SIZE 8 3/8 HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT \_\_\_\_\_  
CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 3/8 OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT IN CASING 250 ft.  
DISPLACEMENT None DISPLACEMENT PSI 0 MIX PSI 0 RATE 4665

REMARKS: Topog Rmpts 250 ft. MAVED 103 sks 60/40 P02-MIX + 490 gal  
Consolidated Cement to Surface - Pulled tubing - Top 8 3/8 off.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5403A	1	PUMP CHARGE	655.00	655.00
5406	10	MILEAGE	4.00	40.00
1131	103	sk. 60/40 P02-MIX	11.95	1230.85
1118B	400	lbs Gel	.20	80.00
5407	1	80 lb Delivery	330.00	330.00
3502C	2	80 VAC	90.00	180.00
Subtotal				2515.85
SALES TAX				85.89
ESTIMATED TOTAL				2601.74

RECEIVED  
OCT 14 2011  
KCC WICHITA

Ravin 3737

AUTHORIZATION Rob Wallin TITLE \_\_\_\_\_ DATE 9-23-2011

244531

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



