

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21491-00-00
Spot: NWNESWSW Sec/Twnshp/Rge: 7-33S-25W
1031 feet from S Section Line, 848 feet from W Section Line
Lease Name: IDUN Well #: 7 #1
County: CLARK Total Vertical Depth: 7059 feet

Operator License No.: 33392
Op Name: KEITH F. WALKER OIL & GAS CO., LLC
Address: 219 STANLEY ST PO BOX 1725
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4420		WITH 10 SX CMT
COND	20	94		WITH 180 SX CMT
PROD	8.625	1171		WITH 510 SX CMT
PROD	5.5	7059	1715	WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2011 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: STEVE DIXON Company: KEITH WALKER OIL & GAS Phone: (580) 223-1575

Proposed Plugging Method: SET CIBP @ 4420' WITH 10 SX CMT. PLUG AT 1200' LOAD HOLE WITH MUD & PUMP 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2011 10:35 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4420' WITH 10 SX CMT. 1ST PLUG AT 1200' WITH 200# HULLS, 15 SX GEL & 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6720	6729		
6644	6760		
5442	5447		
5130	5136		
4469	4476		

RECEIVED
AUG 01 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUL 26 2011

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

Form 08-23