

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21482-00-00
Spot: NESWSENV Sec/Twnshp/Rge: 18-33S-25W
2051 feet from N Section Line, 1814 feet from W Section Line
Lease Name: FREYJA Well #: 18 #1
County: CLARK Total Vertical Depth: 7059 feet

Operator License No.: 33392
Op Name: KEITH F. WALKER OIL & GAS CO., LLC
Address: 219 STANLEY ST PO BOX 1725
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5400		WITH 10 SX CMT
CIBP		5447		
CIBP		6729		
SURF	8.625	1134		WITH 520 SX CMT
COND	20	92		WITH 300 SX CMT
PROD	5.5	7059	2991	WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/20/2011 9:30 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: BARRY JONES Company: KEITH WALKER OIL & GAS Phone: (580) 504-3276

Proposed Plugging Method: SET CIBP @ 5400' WITH 10 SX CMT. PLUG AT 1170' WITH MUD & 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2011 10:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 5447' & 6729'. SET CIBP @ 5400' WITH 10 SX CMT. 1ST PLUG AT 1170' LOAD HOLE WITH MUD & PUMP 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6865	7005		VIOLA
5410	5705		CHESTER

Remarks: USED 60/40 POZMIX 4% GEL BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

RECEIVED
AUG 01 2011
KCC WICHITA

District: 01

RECEIVED
JUL 26 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)