

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21041-00-00  
Spot: SWSE Sec/Twnshp/Rge: 17-30S-33W  
660 feet from S Section Line, 2030 feet from E Section Line  
Lease Name: ERIC BRADLEY Well #: 1-17  
County: HASKELL Total Vertical Depth: 5575 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1629		WITH 25 SX CMT
SURF	8.625	1585		WITH 625 SX CMT
DVT		3268		WITH 525 SX CMT
PROD	5.5	5575	0	WITH 795 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2011 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 1629' WITH 25 SX CMT. RIH W/TBG TO 650' & FILL 5 1/2" CASING TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/25/2011 12:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

CIBP @ 1629' WITH 25 SX CMT. FLUID LEVEL AT 410' FROM SURFACE. RIH W/TBG TO 650'. PUMPED 83 SX CMT. NEVER CIRCULATED. TIED ONTO BACKSIDE & PUMPED 7 SX CMT. PRESSURED TO 500 PSI. SDON. 7/25/11: TAGGED TOC @ 460'. PUMPED 50 SX CMT, FILLING 5 1/2" CASING TO SURFACE. PRESSURED TO 500 PSI. HELD OK.

Perfs:

Top	Bot	Thru	Comments
5136	5152		
5108	5113		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED  
AUG 01 2011  
KCC WICHITA

District: 01

RECEIVED  
JUL 26 2011  
KCC DODGE CITY

Signed Jack MacClaskey  
(TECHNICIAN)

Form CP-211