

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10100-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 35-32S-41W
1362 feet from S Section Line, 4046 feet from E Section Line
Lease Name: BOWKER GAS UNIT A (B-1) Well #: 1-2
County: MORTON Total Vertical Depth: 5330 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5075		
CIBP		5200		WITH 3 SX CMT
SURF	9.625	1493		WITH 1000 SX CMT
PROD	7	5325	1706	WITH 1100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/07/2011 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KENNY ANDREWS Company: OXY USA Phone: (620) 629-4232

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 1530' WITH 80 SX CMT. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE
Date/Time Plugging Completed: 07/07/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5200' WITH 3 SX CMT. 1ST PLUG AT 1530' WITH GEL CIRCULATED THEN 80 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5242	5252		KEYES
5122	5128		SQUEEZED

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
JUL 19 2011
KCC DODGE CITY

RECEIVED
AUG 01 2011
KCC WICHITA

Form CP 22