

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20178-00-01
Spot: SENE Sec/Twnshp/Rge: 12-33S-32W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: LEBEN MCVEY Well #: 1-12
County: SEWARD Total Vertical Depth: 5676 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2770		WITH 2 SX CMT
CIBP		2940		
CIBP		4220		
SURF	8.625	1539		WITH 700 SX CMT
PROD	5.5	4507	2000	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/13/2011 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2770' WITH 2 SX CMT. PLUG AT 1590' WITH 15 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/14/2011 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 2770' WITH 2 SX CMT. CUT CASING & POOH TO 1590'. 1ST PLUG AT 1590' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4412	4418		LANSING
4170	4174		TOPEKA
2816	2860		FT. RILEY

RECEIVED
AUG 01 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA NO LEASE** USED 60/40 POZMIX 4% GEL BY BASIC CEMENTERS.

Plugged through: CSG

District: 01

RECEIVED

JUL 19 2011

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

FORM 84-70