

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21878-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 24-33S-32W  
4796 feet from S Section Line, 3170 feet from E Section Line  
Lease Name: WINCHELL Well #: 1A-24  
County: SEWARD Total Vertical Depth: 2730 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2500		WITH 2 SX CMT
CIBP		2670		
SURF	8.625	560		WITH 250 SX CMT
PROD	4.5	2729	0	WITH 475 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/19/2011 4:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2500' WITH 2 SX CMT. PLUG AT 1440' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/19/2011 8:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*BOND LOG SHOWS TOC @ SURFACE.\*\* CIBP @ 2500' WITH 2 SX CMT. FILL 4 1/2" CASING WITH CMT FROM 1500' TO 0' USING 80 SX CMT. PRESSURED TO 500# & HELD. ANNULUS CEMENTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2681	2684		
2613	2640		
2582	2592		
2548	2562		

RECEIVED  
AUG 01 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA NO LEASE\*\* USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

RECEIVED  
JUL 26 2011  
KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)