

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20196-00-00  
Spot: SENE Sec/Twnshp/Rge: 12-33S-32W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: RD MCVEY Well #: 1  
County: SEWARD Total Vertical Depth: 4235 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2636		WITH 2 SX CMT
SURF	9.625	1475		WITH 800 SX CMT
PROD 7		4250	0	WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/15/2011 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/15/2011 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2636' WITH 2 SX CMT. TEST 7" CASING TO 500# & HELD. PERFORATE 2 HOLES AT 1510'. INJECTION RATE 1 1/2 BPM @ 200#. CIRCULATE CASING & ANNULUS FULL OF CMT WITH 400 SX CMT. CIRCULATED 10 SX CMT TO PIT.

Perfs:

Top	Bot	Thru	Comments
3015	3182		COUNCIL GROVE
2816	2844		FT. RILEY
2770	2800		TOWANDA
2686	2705		WINFIELD

RECEIVED  
AUG 01 2011

KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA NO LEASE\*\* USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

JUL 26 2011

KCC DODGE CITY

Form CP-2(3)