

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-21087-00-00
Spot: NENENW Sec/Twnshp/Rge: 24-30S-41W
330 feet from N Section Line, 2190 feet from W Section Line
Lease Name: ARMSTRONG Well #: 1-24
County: STANTON Total Vertical Depth: 5580 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5437		
CIBP		5490		
SURF	8.625	1657		WITH 550 SX CMT
PROD	5.5	5580	3230	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2011 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580)254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1680' WITH GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 150# HULLS & 25 SX CMT INTO PERFS AT 5376'. SHOT 5 1/2" CASING AT 3230'. 1ST PLUG POH TO 1680', CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5512	5524		ST. LOUIS
5364	5370		KEYES

RECEIVED
AUG 01 2011
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

JUL 19 2011

KCC DODGE CITY

Form 1-24