

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20929-00-00
Spot: NESWNE Sec/Twnshp/Rge: 16-30S-41W
3660 feet from S Section Line, 1615 feet from E Section Line
Lease Name: ROBB TRUST Well #: 16-32
County: STANTON Total Vertical Depth: 5563 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5405		WITH 2 SX CMT
CIBP		5484		
CIBP		5490		
SURF	8.625	1608		WITH 745 SX CMT
DVT		4196		WITH 450 SX CMT
PROD	4.5	5560	0	WITH 299 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2011 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DAVID B PAULY Company: C.H. TODD Phone: (316) 250-2045

Proposed Plugging Method: SET CIBP @ 5405' WITH 2 SX CMT. SHOOT 4 1/2" CASING @ APPROX. 1450'. PUMP 50 SX CMT. POH TO 550' PUMP 50 SX CMT. FILL SURFACE FROM 40'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2011 7:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5405' WITH 2 SX CMT. SHOT CASING AT 1456', UNABLE TO PULL. SHOT CASING AT 1115' UNABLE TO PULL CASING. RIH W/TBG TO 1450' ATTEMPTED TO CIRCULATE HOLE WITH WATER (TOOK 4 1/2 BBL TO LOAD) PRESSURED TO 700 PSI, WITH NO CIRCULATION. PUMPED 50 SX CMT AT 1450'. POH WITH TBG. PERFORATE 4 1/2" AT 560'. CIRCULATED HOLE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5498	5535		ST GEN
5452	5458		KEYES

RECEIVED
AUG 01 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL CONSOLIDATED OILWELL SERVICES.

Plugged through: CSG

District: 01

RECEIVED

JUL 26 2011

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)