

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-091-21751-00-00  
Spot: NENWSWNE Sec/Twnshp/Rge: 30-14S-22E  
3733 feet from S Section Line, 1975 feet from E Section Line  
Lease Name: GILLESPIE Well #: C-5  
County: JOHNSON Total Vertical Depth: 943 feet

Operator License No.: 31847  
Op Name: BRADLEY OIL COMPANY  
Address: PO BOX 21614  
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	20		6 sx
PROD	2.875	926		101 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2010 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: BRADD SCHWARTZ Company: BRADLEY OIL COMPANY Phone: (405) 823-8136

Proposed  
Plugging  
Method:

Consolidated will fill in with cement from bottom to top.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 10/20/2010 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 1" PIPE DOWN TO 570' INSIDE THE 2 7/8" CASING AND COULD NOT GET PASSED JUNK IN HOLE. PUMPED 15 SACKS OF CEMENT FROM 570' TO SURFACE THROUGH 1" PIPE. PULLED 1" PIPE OUT OF THE WELL. HOOKED ON TO 2 7/8" CASING AND SQUEEZED 15 SACKS OF CEMENT. THE WELL HAD A SHUT-IN PRESSURE OF 1000 PSI.

RECEIVED  
L 2 r TCH  
KCC Chanute Dist. #3

Perfs:

Top	Bot	Thru	Comments
887	892		

RECEIVED  
AUG 01 2011  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman  
(TECHNICIAN)