

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05787-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 21-11S-17W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BEMIS A Well #: 2  
County: ELLIS Total Vertical Depth: 3460 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	1167	0	w/unknown sxs cmt
COND	16	65		
PROD	7	3458	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2011 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: GERARD HOLINDE Company: NOBLE ENERGY, INC. Phone: (303) 228-2076

Proposed Plugging Method: Ordered 900 sxs 60/40 pozmix - 4% gel - 600# hulls - 17 sxs gel.  
High fluid level.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2011 12:50 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Superior Wireline Services shot two hole perfs at 1650' and 1150'.  
D.S.&W. RIH with tubing to 3400'.  
Basic Cementing rigged to tubing and pumped 17 sxs gel - followed with 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1672' - rigged to tubing and pumped 350 sxs cement with 200# hulls mixed in to circulate cement up 7" casing.  
Pulled tubing - rigged to 7" casing with a swedge and pumped 200 sxs cement with 100# hulls to circulate up 10" casing.  
Shut in 10" casing. Max. P.S.I. 100#. S.I.P. 100#.  
No 16" casing was visible in the hole.

**Perfs:**

Top	Bot	Thru	Comments
3458	3460		Arbuckle

Remarks: BASIC ENERGY SERVICES-TICKET #04480A

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED Form CP-2/3

AUG 01 2011

KCC WICHITA

JUL 28 2011