

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-04611-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 29-21S-1W  
3001 feet from S Section Line, 5006 feet from E Section Line  
Lease Name: HUXMAN JP Well #: 2  
County: MCPHERSON Total Vertical Depth: 3438 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	149		165 sx
PROD 6		3242		300 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2010 9:30 AM  
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC  
Proposal Rcvd. from: BRYAN HESS Company: \_\_\_\_\_ Phone: (620) 241-4640

Proposed  
Plugging  
Method:

AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/14/2011 11:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

6/9/11 SCOTT'S RAN TUBING TO 2800' AND CONSOLIDATED TIED ON AND SPOTTED 35 SX. THEY THEN LAID OUT TUBING. DYNALOG PERFORATED CASING @ 400' WITH 4 SHOTS. CONSOLIDATED TK #30608 FOR 35 SX 60/40 POS W/ 4% GEL. 6/10/11 HESS DUG OUT THE SURFACE CASING HEAD, AND SCOTT'S RAN TUBING TO 402'. CONSOLIDATED TIED ON AND BROKE CIRCULATION WITH WATER. THEY SWITCHED TO CEMENT AD CIRCULATED TO SURFACE. OVER PUMED CEMENT IN CELLAR. SCOTT'S PULLED TUBING AND TOPPED OFF HOLE. 6/14/11 I CHECKED TOP PLUG FOUND BACKSIDE STANDING FULL BUT CEMENT PLUG IN CASING GONE. I FOUND FLUID DOWN ABOUT 600'. OPERATOR ORDERED OUT 4 YDS OF SLURRY AND FILLED UP THE CASING. I CHECKED TOP PLUG CEMENT @ SURFACE.

Remarks: WELL PLUGGED DUE TO CASING LEAK.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

AUG 03 2011

KCC WICHITA  
Form CP-2/3

JK