

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-02137-00-00
Spot: NESWNW Sec/Twnshp/Rge: 29-21S-1W
3676 feet from S Section Line, 4351 feet from E Section Line
Lease Name: HUXMAN Well #: 13
County: MCPHERSON Total Vertical Depth: 3510 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		200 SX
PLG		420		CASING PARTED??
PROD	5.5	3501		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2011 8:30 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2011 11:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:

7/19/11 SCOTT'S CAN NOT GET DOWN PAST 420'. IT APPEARS THEY ARE GOING OUTSIDE OF CASING @ THIS POINT. J KLOCK (DIST 2) GAVE PLUGGING ORDERS TO PLUG FROM 400' TO SURFACE. DYNALOG OUT AND PERFERD 4 SHOTS FROM 410' TO 411'. 7/20/11 SCOTT'S RAN TUBING DOWN TO ABOUT 395' TAGGED. THEY PICKED UP AND TURNED TUBING AND WENT DOWN ANOTHER 20'. THEY TAGGED SOLID. CONSOLIDATED TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT AND CIRCUALTED THE HOLE FULL. SCOTT'S PULLED TUBING AND CONSOLIDATED TOPPED OFF THE WELL. CONSOLIDATED TK #31155 182 SX OF 60/40 POS W/4% GEL & 1% CC. 7/21/11 I CHECKED TOP PLGU AND FOUND IT DOWN 12'. TOMMY BRUCE WILL DRY SACK IT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3403	3411	CSG	SIMPSON

Remarks: PBTD @ 3455'. WELL PLUGGED DUE TO CASING LEAK.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

AUG 03 2011

KCC WICHITA
Form CP-2/3

12K