

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-30000-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 31-18S-2W
426 feet from S Section Line, 2299 feet from E Section Line
Lease Name: CLARK Well #: 3
County: MCPHERSON Total Vertical Depth: 3040 feet

Operator License No.: 33948
Op Name: C & J PRODUCTION LLC
Address: 4 FAIRWAY DR
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	143		
PROD	7	3040		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/30/2011 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: MIKE'S TESTING & SALVAGE, INC. Phone: _____

Proposed
Plugging
Method:

AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2011 1:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

6/30/11 KELSO HAVE TUBING ON BOTTOM. COPELAND TIED ON AND PUMPED 75 SX OF COMMON AND 200 LBS HULLS FOR BOTTOM PLUG. KELSO'S LAID OUT TUBING AND PERFORATORS PERFED @ 475' AND @ 250'. KELSO'S THEN RAN TUBING TO 472' AND COPELAND SPOTTED 50 SXS. KELSO'S PULLED TUBING TO 250'. COPELAND TIED ON AND CIRCULATED CEMENT TO TOP OF CASING. DID NOT GET CEMENT TO CIRCULATE UP BACKSIDE. I HAD KELSO'S PULL TUBING. COPELAND TIED ON TO THE CASING AND PUMPED ANOTHER 50 SX, STILL NO CIRCULATION. I TALKED WITH KURT ABOUT CUTTING OFF CASING HEAD AND 1" DOWN THE BACKSIDE. WE WILL TRY THIS TOMORROW. 7/1/11 KELSO'S RAN 1" TO 250' AND COPELAND TIED ON AND CIRCULATED CEMENT TO SURFACE. 7/8/11 CEMENT DOWN 8'. KELSO'S WELL DRY SACK TO SURFACE WHEN THEY CUT IT OFF BELOW GRADE.

Perfs:


Top	Bot	Thru	Comments
3002	3006	CSG	

Remarks: EMERGENCY PLUGGING CASING PARTED @ APPROX 2000'

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED

AUG 03 2011

KCC WICHITA Form CP-2/3

AK