

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25278-00-00  
Spot: NESESWSE Sec/Twnshp/Rge: 7-19S-23W  
335 feet from S Section Line, 1598 feet from E Section Line  
Lease Name: JHAAD Well #: 2  
County: NESS Total Vertical Depth: 4385 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		WITH 150 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2011 6:30 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 07/18/2011 8:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
JUL 28 2011  
KCC DODGE CITY

RECEIVED  
AUG 03 2011  
KCC WICHITA