

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21070-00-00
Spot: SENESE Sec/Twnshp/Rge: 5-20S-1W
1660 feet from S Section Line, 334 feet from E Section Line
Lease Name: VOGTS Well #: E 1
County: MCPHERSON Total Vertical Depth: 3446 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 218 | | 175 SX |
| PROD | 5.5 | 3422 | | 150 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/07/2011 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: MIKES TESTING & SALVAGE, INC. Phone: (316) 263-5785

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2011 12:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

7/6/11 KELSO'S DROPPED SAND AND CAPPED W/5 SX. 7/7/11 PERFORATED @ 400' AND RAN TUBING TO 410'. COPELAND TIED ON AND STARTED PUMPING CEMENT 25 BBL STARTED GETTING CIRCULATION UP THE BACKSIDE. THEY CIRCULATED CEMENT TO SURFACE. KELSO'S PULLED TUBING AND COPELAND TOPPED OFF WELL. COPELAND TK #37721 225 SX 60/40 POS W 4% GEL. 7/14/11 I CHECKED TOP PLUG AND FOUND IT 30' DOWN. I NOTIFIED OPERATOR. THEY WILL TOP OFF WELL WHEN THEY CUT OFF THE CASING.

Perfs: _____

Remarks: DENIED TA DUE TO SHUT IN OVER 10 YEARS

Plugged through: TBG

RECEIVED
AUG 03 2011
KCC WICHITA

District: 02

Signed  (TECHNICIAN)

JK