

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21070-00-00  
Spot: SENESE Sec/Twnshp/Rge: 5-20S-1W  
1660 feet from S Section Line, 334 feet from E Section Line  
Lease Name: VOGTS Well #: E 1  
County: MCPHERSON Total Vertical Depth: 3446 feet

Operator License No.: 5399J  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		175 SX
PROD	5.5	3422		150 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2011 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: MIKES TESTING & SALVAGE, INC. Phone: (316) 263-5785

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2011 12:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:


7/6/11 KELSO'S DROPPED SAND AND CAPPED W/5 SX. 7/7/11 PERFORATED @ 400' AND RAN TUBING TO 410'. COPELAND TIED ON AND STARTED PUMPING CEMENT 25 BBL STARTED GETTING CIRCULATION UP THE BACKSIDE. THEY CIRCULATED CEMENT TO SURFACE. KELSO'S PULLED TUBING AND COPELAND TOPPED OFF WELL. COPELAND TK #37721 225 SX 60/40 POS W 4% GEL. 7/14/11 I CHECKED TOP PLUG AND FOUND IT 30' DOWN. I NOTIFIED OPERATOR. THEY WILL TOP OFF WELL WHEN THEY CUT OFF THE CASING.

Remarks: DENIED TA DUE TO SHUT IN OVER 10 YEARS

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
AUG 03 2011  
KCC WICHITA

JK