

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-053-20, 806-00-00

NW, Sec. 28, T 14 S, R 9 W/E

2310 feet from N/E section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Janda Well # 1

Operator: Rains + Williamson Oil Co., Inc.
Name & Address 435 Page Court
220 W. Douglas
Wichita, Kansas 67202

County Ellsworth

Well Total Depth 3075 feet

Conductor Pipe: Size _____ feet \$99.94

Surface Casing: Size 8 3/8 feet 268

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Operator and Sun Oilwell Co. License Number 5146 Reg # 60

Address _____

Company to plug at: Hour: 2:00 AM Day: 23 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Larry Hinderliter

(company name) Rains + Williamson Oil Co., Inc. (phone) 316-793-9075

were: Fill hole with heavy mud. Pump 50 sacks cement through
drill pipe at 500'. Pump 30 sacks cement through drill
pipe at 275'. Fill hole with mud to 40'. Push plug and
1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Cement rat hole with 10 sacks cement.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 AM Day: 23 Month: April Year: 1983

ACTUAL PLUGGING REPORT _____

Same as above

Remarks: Sun Oilwell Cementing Ticket # 15147

Cement used: 50/50 Pozmix w/2% gel and 3% cc.

(Telephone Duty)

I hereby certify that the above plugging instructions were given as herein stated and that I (~~was~~ / did not) observe this plugging.

RPW

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 5-4-83

INV. NO. 4178-W