

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20689-00-00
Spot: NWNENE Sec/Twnshp/Rge: 10-13S-32W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: TEETER Well Number: 1
County: LOGAN Total Vertical Depth: 4729 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 A WEST MAIN ST.
SALEM, IL 62881

Conductor Pipe: Size _____ feet: \$153.69
Surface Casing: Size 8.625 feet: 235
Production: Size _____ feet:
Liner: Size _____ feet:

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/02/2002 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/02/2002 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2550' w/25 sxs. Anhydrite 2520' - 2560'.
2nd. Plug at 1500' w/100 sxs. Dakota 1176' - 1476'.
3rd. Plug at 285' w/40 sxs. Surface pipe at 235'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
OCT 16 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

10-16-02

2003060647

OCT 14 2002