

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-109-20,264-00-00
SW, Sec. 21, T 12 S, R 33 WE
2310 feet from N/S section line
990 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Ahrens Well # 61

Operator: Lawson, Donald C., Oil Producer
Name & Address 200 Douglas Bldg. Wichita, Ms. 67202

County Logan

Well Total Depth 4800' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 395'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Lawson Drilling Co. License Number 240

Address 200 Douglas Bldg. Wichita, Ms. 67202

Company to plug at: Hour: 7:00 AM Day: 17 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO J. Loppil

(company name) Lawson Drilling Co. (phone) 316-2633201

were: Order 180 sacks 50 percent - 6% Sol. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 2600' w/ 20 sh. 2nd plug @ 1100' w/ 100 sacks. 3rd plug @ 450' w/ 40 sacks. 4th plug solid bridge of balls & plug @ 40' w/ 10 sacks. Circulate 10 sacks in set hole.

Signed J. H. Loppil (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 AM Day: 17 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 395' SP. w/ 275 sacks common - 2% Sol. - 3% Cal. Cl.
Ordered 180 sacks 50 percent - 6% Sol. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 2600' w/ 20 sh. 2nd plug @ 1100' w/ 100 sh. 3rd plug @ 450' w/ 4 sh. 4th plug solid bridge of balls & plug @ 40' w/ 10 sh. Circulated 10 sh. in set hole.

Remarks: _____

RECEIVED STATE CORPORATION COMMISSION

DEC 21 1982

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed J. H. Loppil (TECHNICIAN)

1-30-83
2237-W