

159
R

4-070970

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,520-00-00

SW SW /4 SEC. 32, 15 S, 37 W
660 feet from S section line
4620 feet from E section line

Operator license# 08914

Lease Niswonger well # 1-32

Operator: H & C Oil Operating, Inc.

County Logan

Address: P.O. Box 86
Plainville, Kansas 67663
Charles R. Ramsay

Well total depth 5125 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 180 feet

166.56

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Drilling Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 31 Month: October Year: 91

Plugging proposal received from: D. L. Finney

Company: Emphasis Drilling Company Phone: 913-434-7434

Were: 8 5/8" 311' S.P. cwc. w/180 sx. 60/40 posmix - 2% gel. -
3% cal.cl. By Allied Cement. No circulate problems. Mud condition
43 vis. - 9.0 wt. - 10 W.L. Elv. 3429' - Anhy. 2661'. Proposal 200 sx.
60/40 posmix - 6% gel. - 1 sx. F.C. Spot with drill stem. Circulate
hole. Spot heavy mud between all plugs. 25 sx. @ 2670' - 100 sx. with
1 sx. F.C. @ 1480' - 40 sx. @ 360' - 10 sx. @ 40'.
15 sx. Rathole. 10 sx. Mousehole. Circulate.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All [] , Part [] , None []

STATE CORPORATION COMMISSION
RECEIVED
NOV 25 1991

Completed: Hour: 3:00P.M. Day: 31 Month: October Year: 91

Actual plugging report: Emphasis Drilling ordered 200 sx. 60/40
posmix - 6% gel. - 3% cal.cl. Spot with drill stem, circulate hole.
Heavy mud between all plugs.

1st. plug 25 sx. @ 2670'.
2nd. plug 100 sx. w/1 sx. flocele @ 1480'.
3rd. plug 40 sx. @ 360'.
4th. plug 10 sx. @ 40'.
15 sx. in Rathole (circulate) - 10 sx. in Mousehole (circulate)

Remarks: Cemented by: Allied Cementing.

I did [] / did not [X] observe the plugging.

Marion J. Schmidt
(agent)

Form CP-2/3

INVOICED

DATE 12-5-91
INV. NO. 33942

File S