

4-020098

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-109-206,24-0000

60'E, 60'S of N2N2S2 /4 SEC. 29 , 15 S, 34 W  
2250 feet from S section line  
2700 feet from E section line

Operator license# 05123

Lease: Tucker "C-D" Well # 1

Operator: Pickrell Drilling Co., Inc.  
Address: 110 N. Market, Suite 205  
Wichita, Kansas 67202

County: Logan 157.62  
Well total depth 4850 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 360 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Pickrell Drilling Co., Inc. License# 05123

Address: 110 N. Market, Suite 205, Wichita KS 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 09 Month: May Year: 1996

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Co., Inc. Phone: 316 262 8427

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2400 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1240 feet with 100 sacks

3rd plug @ 410 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 3:30 AM, Day: 09, Month: May, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC X, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 3044 GL

Did (agent) observe the plugging? Yes (agent) \_\_\_\_\_

**INVOICED**

DATE \_\_\_\_\_  
INV. NO. 45694

100

MAY 14 1996

05-14-96  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3