

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 109-20, 262-00-00

SW-SW-NE, Sec. 27, T 15 S, R 34 W/E

2135 feet from N/8 section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name MCDANIEL Well # A-1

Operator: CITIES SERVICES CO.  
Name & Address: 800 SUTTON PLACE, BLDG.  
209 EAST WILLIAM  
WICHITA, MO. 67202

County LOGAN

Well Total Depth 4800 feet

Conductor Pipe: Size 0 feet 0

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG INC License Number # 182

Address 801 UNION CTR. WICHITA, MO. 67202

Company to plug at: Hour: 12:30 PM Day: 10 Month: NOV. Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO BILL CRUIG

(company name) ABERCROMBIE DRUG Co (phone) 316-262-1841

were: 8 5/8" - 384' SR CUL w/ 300' COMMON - 2% GEL - 3% CA-CL (BY SUN CMT)  
ORDER - 180' 50/50 FORMIX 6% GEL - 3% CA-CL, AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2340' w/ 20' CMT. -> 2nd PLUG @ 1200' w/ 100' CMT

3rd PLUG @ 420' w/ 40' CMT. 4th PLUG. SOLID BRICK MULL'S - PLUG @ 40' w/ 10' CMT

10' IN RAT HOLE (CIRCULATE)

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:00 AM Day: 10 Month: NOV Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 384' SR CUL w/ 300' COMMON (BY SUN CMT)

ORDERED 180' 50/50 FORMIX 6% GEL - 4% CA-CL, AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2340' w/ 20' CMT. -> 2nd PLUG @ 1200' w/ 100' CMT

3rd PLUG @ 420' w/ 40' CMT. -> 4th PLUG SOLID BRICK MULL'S - PLUG @ 40' w/ 10' CMT

10' IN RAT HOLE (CIRCULATE) (CEMENTED BY SUN CMT)

Remarks: DID NOT PENETRATE ABERCROMBIE

RECEIVED  
STATE CORPORATION COMMISSION

NOV 22 1982 11-22-82

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

11-24-82  
1726-W