

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-109-20,174-00-00

CSW NW SEC. 28, T 15 S, R 35 (W)

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line

4620 feet from E section line

Operator License # 5447

Lease Name MILLER AB Well # 1

Operator: CITIES SERVICE O & G. CORP.

County LOGAN 155.35

Name & Address Box 38

Well Total Depth 4780 feet

HILL CITY, KANSAS

Conductor Pipe: Size _____ feet

6764Z

Surface Casing: Size 8 5/8 feet 839'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CMT CO. License Number _____

Address NESS CITY, KANSAS

Company to plug at: Hour: AM Day: 16 Month: 4 Year: 19 86

Plugging proposal received from J. D. HININGER

(company name) CITIES SERVICE (phone) _____

were: 8 5/8 @ 839' w/550 SX, 5 1/2 @ 4779' w/250 SX. PERE 4384-87, 4391-94

ORDER SAND & COM. CMT., RECOVER PIPE, ORDER 200 SX. DICEL

(ECONOLITE) 5 SX. HULLS ALLIED CMT. CO. NEUMAN WATERTRUCK.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:AM Day: 16 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 4300' SPOT 5SX. COM. CMT. ON SAND

W/BAILER 7 SHOTS RECOVERED 1331' OF 5 1/2"

HOOK UP TO 8 5/8 MIX. & PUMP 4 SX. HULLS 200 SX. ECONOLITE + 1 SX. HULLS

MAX. PSI 500^{##} CLOSE 300^{##} PLUG. COMPLETE

STATE CORPORATION COMMISSION

APR 20 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE APR 29 1986

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. _____