

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20204-00-00
Spot: SWNE Sec/Twnshp/Rge: 21-15S-35W
4620 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: DIRKS D Well Number: 1
County: LOGAN Total Vertical Depth: 4834 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

Conductor Pipe: Size feet: #157.11
Surface Casing: Size 8.62 feet: 364 300 sx cmt
Production: Size 5.5 feet: 4565 650 sx cmt \$157.11
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/15/2001 9:00 AM
Plug Co. License No.: 30931 Plug Co. Name: DAYSTAR PETROLEUM, INC.
Proposal Rcvd. from: BILL SCHMITDT Company: DAYSTAR PETROLEUM, INC. Phone: (316) 755-3523

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/15/2001 10:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8' set at 364' w/300 sxs cwc. 5 1/2" set at 4565' w/250 sxs.
D.V. at 2500' w/400 sxs cwc.
Prod. Perf. 4450' - 4458'.
Casing anchor left in the hole at 4420'.
Squeezed 5 1/2" with 300 sxs cement blend with 300# hulls mixed in.
No P.S.I. Plug held.
8 5/8" had cement to surface.

NOTICE
DATE 03-08-2001
FILE NO. 209061458

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

JD

Signed

Carl Goodrow

(TECHNICIAN)

RECEIVED

STATE CORPORATION COMMISSION

FEB 27 2001

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

FEB 20 2001

replacement card

CITIES SERVICE OIL CO
WICHITA KS

21-15S-35W
SW NE NE

#1 DIRKS D

site 11-1/4 S & 1 W OF RUSSELL SPRINGS KS city: LOGAN API 15-109-20204
cstr: RAINS & WILLIAMSON field DIRKS NE CONF & EXT (1/4 W)

well:
fr date 11/30/1981 spd date 12/12/1981 drig comp 12/29/1981 card issued 03/11/1982 last revised 11/27/2000

ELV: 3209 KB, 3200 GL LOG

tops.....	depth/datum
SC.....	2440 +769
B/SC.....	2528 +681
TOP.....	3751 -542
HEEB.....	3972 -763
TOR.....	3995 -786
LANS.....	4022 -813
DENNIS SD.....	4293 -1084
ALT.....	4449 -1240
PAW.....	4469 -1260
FT SC.....	4535 -1326
CHER.....	4552 -1343
MRW.....	4711 -1502
MISS.....	4786 -1577

IP status
OIL, P 50 BO & 4 BWPD, MARM 4450-4458 , 03/04/1982
LTD.....4831 -1622
RTD.....4834 -1625
CORRECTION: 11/27/2000 - ORIG.FP IN C NE NE
CSG: 8-5/8" 364 / 300'SX, 5-1/2" 4565. DV TOOL AT 1500
NO CORES .
DST (1) 4439-4459 (MARM), / 30-60-30-60, 465' GIP, REC 560'
OIL, 220' SLI MCO (GR 37) ISIP 499# FSI P 480# IFP 98#
-196# FFP 196# -294# BHT 110'
TRGT ZN: MARM, MISS (OIL/GAS), PTD 4800 (MISS), MICT -
CO, PF (ALT) 4450-4458, W / 16 SPF, AC 2000 GAL, SWB LD
& REC 3.2 BFPH (97% OIL), POP, P 50 BO & 4 BWPD,
3/4/1982

COPYRIGHT 2000
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS