

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-01,000-00-01

NWSW, SEC. 4, T. 14S, R. 38W

1960 feet from S section line

4580 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name PEARCE Well # 1 (OWWO)

Operator Name: TXO PRODUCTION CORP

County WALLACE 171.85

Address 155 N MARKET STE 1000

Well Total Depth 4910 feet

WICHITA KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 192

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated OWWO

Plugging Contractor MURFIN DRILG. CO. License Number 6033

Address WICHITA, KANSAS

Company to plug at: Hour: AM Day: 10 Month: 25 Year: 19 85

Plugging proposal received from JERRY COLLINS

(company name) TXO (phone) \_\_\_\_\_

were: 8 5/8 SET @ 192 CWC WITH HOLE FULL OF NO LESS THAN  
36 UIS. MUD. SPOT CEMENT PLUGS WITH DRILL PIPE. ORDER,  
190 SX. 60/40 POL. 6% GEL 3% B. 8 5/8 W.P. BJTITAN CEMENT CO.  
WATER FROM SMOKEY HILL RIVER

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:30AM Day: 25 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P @ 2540 DISPLACE 25 SX. CMT MIX. LAYDOWN  
D.P. TO 1500' DISPLACE 100 SX. CMT. MIX. 71 SX. HULLS LAYDOWN D.P.  
TO 225' DISPLACE 40 SX. CMT. MIX LAYDOWN D.P. PUSH W.P. TO  
KELLY DEPTH Dump 1/2 SX. HULLS 10 SX. CMT MIX TO BASE OF CELLAR  
DISPLACE 15 SX. CMT MIX IN RATHOLE W/ JOINT OF PIPE PLUG. COMPLETE

Remarks: ELEV 3300' and by 2540

(If additional description is necessary, use BACK of this form.)

**INVOICED**

**RECEIVED**

STATE CORPORATION COMMISSION

DATE NOV 26 1985

NOV 20 1985 Signed

Carl Goodrow  
(TECHNICIAN)

5-16-85  
mpg

11230

CONSERVATION DIVISION  
Wichita, Kansas

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

\* CORRECTION\* 10-25-85

Starting Date 10 28 85 month day year

API Number 15- 199-01,000-00-01

OPERATOR: License # 5171
Name TXO Production Corp.
Address 155 N. Market Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Jerry W. Collins
Phone 316-269-7600

Approx N/W S/W Sec 4 Twp 14 S, Rg 38 X East
\* 1960 Ft. from South Line of Section
\* 4580 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Co
City/State Wichita, KS

Nearest lease or unit boundary line 700 feet

County Wallace

Lease Name PEARCE "F" Well # 1 (OWWO)

Ground surface elevation TBD feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield XMud Rotary
Gas Inj X Pool Ext Air Rotary
XOWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Surface pipe by Alternate: 1 2 X

Depth to bottom of fresh water 100

Depth to bottom of usable water 1500

Surface pipe planned to be set 192

Projected Total Depth 4850 feet

Formation Morrow

If OWWO: old well info as follows:
Operator Flynn Oil Co. & F.W. Wyant & Assoc.
Well Name C.F. Pearce
Comp Date 2-1-52 Old Total Depth 5063'

Formation Morrow

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.
Date 10-25-85 Signature of Operator or Agent Jerry W. Collins Date Drlg. & Completion Engr. 10-25-85

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 1 2

This Authorization Expires 4-15-86 Approved By 10-15-85

RECEIVED STATE CORPORATION COMMISSION

NOV 20 1985

CONSERVATION DIVISION Wichita, Kansas

33100 2100