

4-032151

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,118-00-00

SE SE _____ /4 SEC. 35 , 13 , 33 W
660 _____ feet from S section line
660 _____ feet from E section line

Operator license# 5364

Lease: Hildebrand Well # 1

Operator: Beren Corporation

County: Logan

Address: 970 Fourth Financial Center
Wichita, Kansas 67202

Well total depth 4610 149.82 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Oakley, Kansas 67648

Company to plug at: Hour: A.M. Day: 16 Month: May Year: 1996

Plugging proposal received from: Ed

Company: Beren Corporation Phone: _____

Were: Order 275 sxs 60/40 pozmix - 10% gel - 400# hulls.

RECEIVED
KANSAS CORP COM
MAY 24 4 11:26

05-24-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00 A.M., Day: 16, Month: May, Year: 1996

Actual plugging report: 8 5/8" set at 264' cwc with 200 sxs. 4 1/2" set at 4150' with 250 sxs. Prod. Perfs. - 3545' - 3551'. PFTD 4011'. Critical area control shots at 2340' and 1280'. Squeezed 4 1/2" w/225 sxs cement blend w/400# hulls. Mixed into Max. P.S.I. 100#. Close in P.S.I. 0#. Squeezed 8 5/8" - 50 sxs cement blend to Max. P.S.I. 250#. Held. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES 2328 NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____, NO _____

Plugged through TUBING _____, CASING _____ Elevation: 2875 GL

I did[X] / did not[] observe the plugging.

INVOICED

Carl Goodrow
(agent)

Form CP-2/3

DATE JUN 05 1996

INV. NO. 5-16 17 995