

4- 031744

Handwritten initials

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,098-00-00
SW /4 SEC. 35, 13 S, 33 W
1320 feet from S section line
3960 feet from E section line

Operator license# 5393

Lease Smokey Valley well # 3

Operator: A.L. Abercrombie, Inc.

County Logan

Address: Rt. 1
Box 56
Great Bend, Kansas 67530

Well total depth 4520 feet ^{146.90}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 267 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Company License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 17 Month: August Year: 92

Plugging proposal received from: Vernon Duntz

Company: Kelso Casing Company Phone: _____

Were: Order 400 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open by bailer.
Shots @ 2300' and 1230'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 6:00P.M. , Day: 17 , Month: August , Year: 92

Actual plugging report: 8 5/8" set @ 267' w/190sx. 4 1/2" set @ 4520'
w/250 sx. P.B.T.D. 4117'. Perf. 3696' - 3824'. Recovered 1230' of
4 1/2". Pump bottom plug from T.D. to 1300' w/150 sx. to Max. P.S.I.
1050#. Shot pipe and staged cement to surface. Squeezed 8 5/8" with
total 400 sx. cement blend w/500# hulls mixed in to Max. P.S.I. 900#
Close in P.S.I. 200#. Plug complete.

RECEIVED CORPORATION COMMISSION

SFD 16-1992
09-16-92
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES 2318 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2872 GL

I did[] / did not[] observe the plugging. Carl Goodrow

9-29-92
36258

(agent)